### **Restruct Commercial Doors Ltd**

YOUR FIRE DOOR SPECIALISTS

#### SCOTTS CONSTRUCTION - WEST COAST MENTAL HEALTH

#### <u>Leaf Type – STC40 Rated</u>

Panel Type	Core	Face Finish	Capping	Thickness
RCD Acoustic STC40	RCD Designed Core	Paint Finish	RCD Aluminium Cap	54
RCD Acoustic STC40	RCD Designed Core	HPL Finish	RCD Aluminium Cap	54

#### **Leaf Capping Options**

Single STC40 - Acoustic Rated Door



Double STC40 - Acoustic Rated Door





#### **Door Jamb Type**

RCD 1 Piece Steel Jamb, Powder Coated

**RP124 Parameter Seal** 








Rana Hammond Director - 50 North Eyre Rd Swannanoa - Cell 021 400 655

rana@restructconstruction.co.nz


### **Restruct Commercial Doors Ltd**

YOUR FIRE DOOR SPECIALISTS

#### **Fixing Positions**



#### **Bottom View**



## Restruct Commercial Doors Ltd YOUR FIRE DOOR SPECIALISTS

#### Acoustic Door Into Wall Frame



Add Jack Studs To Sides and from Fix Both Sides




Add 13mm Noiseline GIB On Top of Frame



Add Jack Stud To Top and from Fix Both Sides



Fully Prepared Acoustic Door To Go Into Wall Frame




Fix Prepared Acoustic Door Through Framing Studs & Lintels

# Restruct Commercial Doors Ltd YOUR FIRE DOOR SPECIALISTS

#### Noiseline GIB Installation




Insert Noiseline Gib Into Frame GIB Groove All Sides



Noiseline GIB Installed **Both Sides** 



Align Noiseline Gib With Top **GIB** Groove



Fully Installed Acoustic Door



Add Noiseline GIB Into Top GIB Groove


## **Restruct Commercial Doors Ltd**

YOUR FIRE DOOR SPECIALISTS

#### **Drop Seal Positioning**



RP8SI Installed inside the leaf RP99SI Installed On Side Of Leaf Between Door Stops



RP8SI Drop 3-13mm



Automatic Activation On Door Close



RP99SI Fixed Between Door Stops

